

HATCHSIDE · CALCULATION

HatchSide sizing and first-principles checks

Design Molecule Lab · designmolecule.com

DOCUMENT CONTROL

Document ID	HTS-CAL-001	Version	0.1
Status	Draft	Date	2026-10-03
Author	Amish Chadha	License	CERN-OHL-S-2.0
Project TRL	TRL 3 Proof of concept		
Repository	github.com/BoujeeEnjinia1701/hatchside		
Source	docs/04-calcs/01-sizing.md @ uncommitted		

REVISION HISTORY

Version	Date	Author	Change
0.1	2026-10-03	Amish Chadha	First calculation note at TRL 3, from the constructable model (HTS-DDR-002)

HatchSide sizing and first-principles checks

The constructable HatchSide meets every requirement that can be checked on paper. At the design case (150 kg safe working load, times 1.5 for proof, times 1.25 for jerk) the most loaded leg carries 3.85 kN against an Euler buckling load of 21.2 kN, the rope has a safety factor of 14.3 at the safe working load, the tripod tips only when the rope is about 25 degrees off vertical, no packed load exceeds 23.7 kg, and every head except DomeReach passes a 560 mm manhole opening as it hangs (DomeReach passes with its arm folded). The estimated parts cost is USD 2,838 against the USD 5,000 value-engineering target. Corrosion resistance (R11) cannot be shown on paper and is left to a TRL 4 coupon test.

All numbers are first-principles estimates from the model geometry; nothing has been built or measured. The script `docs/04-calcs/sizing.py` reads the geometry from `cad/src/model.py` and the prices from `bom/bom.csv`, prints every number in this note and writes `docs/04-calcs/results.csv`.

Safety: HatchSide lifts loads over an open confined space. These calculations size a material-handling frame for tool heads only. They do not qualify the frame, winch or rope for lifting, lowering or rescuing people, and the design is not certified equipment. A proof-load test with a competent person (CalRig, TRL 4) must come before any use over a real opening.

■ 1. Assumptions

Table 1. Assumptions.

#	Assumption	Value	Basis
A1	Safe working load at the head interface	150 kg	R4
A2	Proof load factor	1.5	R4
A3	Dynamic factor for snatch when a grab breaks free of silt	1.25	Engineering judgement for a hand winch (slow rope speed)
A4	Aluminium 6082-T6 tube: elastic modulus, 0.2 % proof	69,000 MPa, 250 MPa	Handbook values; welds are not used on the legs
A5	S275 plate yield	275 MPa	EN 10025
A6	A4-70 stainless bolt, 0.2 % proof	450 MPa	ISO 3506
A7	6 mm 7x19 grade 316 rope minimum breaking load	21 kN	Conservative catalogue value
A8	Winch rating	450 kg on the first layer, about half on a full drum	Typical two-speed hand winch
A9	Effective drum radius with a few layers on	40 mm	Model drum and rope
A10	Winch gear ratios, crank, efficiency	4:1 and 10:1, 250 mm, 0.75	Typical two-speed hand winch
A11	Comfortable cranking rate	40 rpm	Engineering judgement
A12	Grab fill factor in wet silt	70 %	Estimate
A13	Wet silt density	1.8 kg/L	Estimate
A14	Smallest common manhole clear opening	560 mm	Common street manhole size in India

■ 2. Geometry

The legs are pinned on a 220 mm circle at the head, 2,250 mm above the ground, and on a 3,000 mm circle at the feet. Each leg is 2,585 mm pin to pin and leans 32.5 degrees from vertical. The feet form an equilateral triangle with 2,598 mm sides; the shortest distance from the centre to a side (the tipping edge) is 750 mm. The sheave centre is 2,413 mm above the ground and the top of the mast is 2,515 mm. The sheave is 125 mm across at the rope, so the ratio of sheave to rope diameter is 20.8. The upper and lower legs overlap by 305 mm at normal length and by 230 mm at the longest setting; the adjust pin gives 75 mm either way along the leg.

The sheave height is set so that the rope from the winch drum runs parallel to leg A, 110 mm outside its centre line, and drops vertically on the axis of the opening. This keeps the rope clear of the leg and the head plate without a separate mast.

■ 3. Structure

The design case is the safe working load times the proof factor times the dynamic factor: $1,472 \text{ N} \times 1.5 \times 1.25 = 2,759 \text{ N}$ on the rope. Because the rope also runs from the sheave down along leg A to the winch, the head sees the load downward plus the same pull along leg A. Solving the three leg directions for equilibrium gives the forces in Table 2.

Table 2. Structural checks at the design case (2,759 N on the rope).

Check	Result	Limit or comparison	Margin
Leg compression, leg A (winch leg)	3,850 N		
Leg compression, legs B and C	1,091 N each		
Euler buckling, whole leg taken as the weaker 50 x 3 mm section over 2,585 mm	21.2 kN	3,850 N	5.5
Axial stress in the 50 x 3 mm tube	6.8 MPa	250 MPa	Large
Hinge bolt bearing on the 4 mm upper leg walls	30.1 MPa	About 250 MPa	Large; the steel crush sleeve stops the walls closing
Foot bolt bearing on the 3 mm lower leg walls	40.1 MPa	About 250 MPa	Large
M16 bolt, double shear on the thread root	13.3 MPa	About 260 MPa	Large
Head lug bearing (8 mm S275)	15.0 MPa	About 275 MPa	Large
Vertical force at the feet	3,246 N (A), 920 N (B and C)		
Horizontal thrust at the feet	2,070 N (A), 586 N (B and C)		
Leg-spread chain tension	1,195 N	About 5 kN working limit for 6 mm grade 30 chain (to confirm on purchase)	About 4
M12 stop bolt, single shear	33.8 MPa	About 260 MPa	Large
Stop bolt bearing on the 4 mm leg wall	28.7 MPa	About 250 MPa	Large
Rope safety factor at the safe working load	14.3	5 or more for a material hoist	Met
Rope safety factor at proof load	9.5		Met

Buckling governs the legs, and even then the margin is 5.5 with the whole leg taken as the weaker section. The stresses at the bolts and lugs are low because the joints were sized for handling, stiffness and wear rather than strength. The chain working limit is a typical catalogue figure and is listed in the design decisions register to confirm when the chain is bought.

■ 4. Winch effort and rope speed

With a 40 mm effective drum radius, a 250 mm crank and 75 % efficiency, lifting 150 kg in low gear (10:1) needs a crank force of about 31 N, and lifting a 50 kg loaded grab in high gear (4:1) about 26 N. At 40 rpm the rope moves 2.51 m/min in high gear and 1.01 m/min in low gear. Both forces are comfortable for one person. The winch is a material winch with an automatic load brake, so the load holds when the crank is released.

■ 5. Masses and packed loads (R6)

Masses come from the model solids and the material densities, plus the stated mass of bought parts (winch 9 kg, rope 2.3 kg, chains 6.7 kg, working line 2.1 kg and others).

Table 3. Packed loads.

Load	Contents	Mass
1	Head, mast, sheave, snatch block, hinge bolts, head interface	16.8 kg
2	Upper legs (3) with adjust pins	11.1 kg
3	Lower legs (3) with feet, pads and foot bolts	20.3 kg
4	Winch, bracket, rope, line counter, cleat, working line	18.6 kg
5	Rim guard panels (6), drop pins and leg-spread chains	23.4 kg
6	Grab head	23.7 kg
7	Sampler head	11.4 kg
8	Rake head and retrieval head	18.6 kg
9	DomeReach head (two pole sections, arm, roller)	7.2 kg

The tripod with winch and rope is about 71.4 kg and the whole kit about 151 kg. The heaviest load, the grab, is 23.7 kg, under the 25 kg limit of R6. In use the legs stay bolted to the head (loads 1 and 2 travel together on a cart) and the crew stands the tripod as one piece.

■ 6. Stability (R14)

The tripod tips over the nearest edge of the foot triangle when the moment of a sideways rope pull about that edge exceeds the restoring moment of the rope load and the tripod's own weight. With the sheave 2,413 mm high, the edge 750 mm from the centre and a 71.4 kg tripod, the largest rope angle from vertical before tipping is 24.6 degrees at the safe working load and 22.3 degrees at proof load. The requirement is to stay stable with the rope 10 degrees off vertical, so the margin is more than double. Crews keep the rope within 10 degrees and never drag a load sideways with the winch.

■ 7. Tool heads

Grab (R8). Each clamshell is a quarter cylinder 182 mm inside radius. The two shells together hold 15.4 L; at 70 % fill that is 10.8 L, about 19 kg of wet silt per cycle.

Sampler (R9). The clear tube is 75 mm outside, 3 mm wall and 600 mm long, so it holds 2.24 L. Its centre is 420 mm below the shackle pin and the line counter reads to 0.1 m, so the sample centre is known to within 0.2 m.

DomeReach (R10). With the tiller kept 200 mm above the rim, the arm hinge reaches 2,640 mm below the rim and the end of the arm 3,340 mm. The arm swings out 495 mm at 45 degrees. A household fixed-dome digester depth of 2.5 m is assumed for R10.

Passing the opening (R13). Plan sizes of each head as it hangs (Table 4). Each must fit a 560 mm opening with 20 mm to spare, so the largest plan diagonal allowed is 540 mm.

Table 4. Head plan sizes.

Head	Plan size (mm)	Height (mm)	Plan diagonal (mm)	Passes 560 mm
Grab	370 x 372	772	525	Yes
Sampler	150 x 150	836	212	Yes
Rake	400 x 65	740	405	Yes
Retrieval head	300 x 300	496	424	Yes
DomeReach, arm folded, below the tiller	86 x 258	3,910	272	Yes

■ 8. Grab output and setup time (R5)

At 3 m depth in high gear, one grab cycle (lower, close, lift, swing to the bin) takes about 3.9 minutes, about 15 cycles and about 166 L of silt per hour (estimate). About 10 % drips back down the shaft.

The setup estimate is 9.0 minutes for two people: cone off the site and lift the cover (1.5 min), lay out the feet and chains (1.0), stand the tripod with the legs already bolted to the head (2.0), set the leg pins and check level (1.5), hang the head on the rope already reeved (1.0), and pin the rim guard round the opening (2.0). The winch stays on leg A in transport.

■ 9. Results against the requirements

Table 5. Results (also written to docs/04-calcs/results.csv).

ID	Requirement	Result	Status
R1	No entry for any task	Every head fitted, worked and recovered from the rim	Met on paper
R2	Fits openings 0.5 to 1.2 m	Feet on a 3.0 m circle; rim guard inner face at 672 mm radius	Met on paper
R3	Working depth 10 m	15 m of rope; drum capacity to confirm when the winch is bought	Met on paper
R4	Safe working load 150 kg, proof 1.5 times	Buckling margin 5.5; rope safety factor 14.3	Met on paper
R5	Setup in 10 minutes	9.0 minutes (estimate)	Met on paper (estimate)
R6	No load over 25 kg	Heaviest load 23.7 kg	Met on paper
R7	Head change under 2 minutes without tools	One screw-pin shackle, about 1 minute	Met on paper (estimate)
R8	Grab lifts 10 L per cycle	10.8 L at 70 % fill	Met on paper (estimate)
R9	Sample at depth within 0.2 m	Counter reads 0.1 m; tube centre known	Met on paper
R10	DomeReach reaches the digester floor	Hinge 2.6 m, tool 3.3 m below the rim	Met on paper (depth taken as 2.5 m)
R11	Corrosion resistance	Galvanized steel, 6082 aluminium, A4 fasteners and rope	Not verifiable on paper; TRL 4 coupon test
R12	Value-engineering target	Value-engineering target: USD 5,000. Estimated cost of the constructable design: USD 2,838 (USD 2,162 under the target)	Under the target
R13	Every head passes a 560 mm opening	Largest diagonal 525 mm	Met on paper
R14	Stable with the rope 10 degrees off vertical	Tips at 25 degrees at the safe working load	Met on paper

■ 10. Limits of this note

- The buckling check treats each leg as one pin-ended column of the weaker section. The real telescoped leg is stiffer; the check is conservative.
- Winch performance, drum capacity and rope breaking load are catalogue figures to confirm when the parts are bought.
- Ground bearing is not checked: on soft ground the feet need boards (listed in the build plan's safety stops).
- Fatigue, wear of the sheave bearing and corrosion are TRL 4 questions.